BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38322

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/16/2019-20, Date: 10.10.2019

Construction of drains at Maruthinagara and Bhadrappa Layout in ward no 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHIVAKUMAR N M ( )		
				In Figures		In Words
1	284.19	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2m and an average lift upto 1.5m excavated surface levelled and sides neatl;y dressed, the disposed earth to be levelled neatlyu after breaking of clods complete as per specifications.	cum	137.0	38934.03	Rupees One Hundred Thirty Seven Only
2	36.59	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5150.0	188438.50	Rupees Five Thousand One Hundred Fifty Only
3	767.28	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	sqm	379.0	290799.12	Rupees Three Hundred Seventy Nine Only
4	87.48	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	cum	5770.0	504759.60	Rupees Five Thousand Seven Hundred Seventy Only
5	4.122	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	Tonne	70000.0	288540.00	Rupees Seventy Thousand Only
6	188.82	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications.	Sqm	1700.0	320994.00	Rupees One Thousand Seven Hundred Only
7	241.56	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading with all leads and lifts as directed by the Engineer in charge of the work.	cum	101.0	24397.56	Rupees One Hundred One Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

27/01

29/01